



Town of Estes Park, Colorado

Fall River Corridor Plan for Resiliency

 **Fall River** Coalition



COLORADO

Colorado Water
Conservation Board

Department of Natural Resources

Prepared for:

≡≡≡ Fall River Coalition



®

Town of Estes Park



COLORADO

Colorado Water Conservation Board

Department of Natural Resources

Prepared by:



Environmental Scientists and Engineers, LLC



ANDERSON CONSULTING ENGINEERS, INC.
Civil • Water Resources • Environmental



Table of Contents

Section 1.0	Executive Summary				
Section 2.0	Introduction		3		
	2.1 Project Scope				
	2.2 Community Process Approach				
	2.3 Risk Assessment Approach				
	2.4 Resilient Solution Approach				
Section 3.0	Community Outreach and Involvement		7		
	3.1 Objective				
	3.2 Plan for Resiliency Team				
	3.2.1 Formation and Member Entities				
	3.3 Public Engagement Process				
	3.3.1 Stakeholders				
	3.3.2 Public Meetings				
	3.3.3 River Advisory Committee (RAC)				
	3.3.4 Values & Evaluation Criteria Survey				
	3.3.5 Project Website and Facebook Pages				
Section 4.0	Watershed Background and Description		11		
	4.1 Location				
	4.2 Flood History				
	4.2.1 Historic				
	4.2.2 September 2013 Flood				
Section 5.0	Data Collection		15		
	5.1 GIS Data and Mapping				
	5.2 Identified Reaches				
	5.3 Field Work				
	5.4 Values & Evaluation Criteria Survey				
	5.5 Related Plans and Documents				
	5.6 Regulatory Floodplains				
Section 6.0	River Corridor Risk Assessment				21
	6.1 Overview				
	6.2 Ecosystem Risk Assessment				
	6.2.1 Methodology				
	6.2.2 Results				
	6.2.2.1 Channel Stability				
	6.2.2.2 Water Quantity				
	6.2.2.3 Water Quality				
	6.2.2.4 Vegetation				
	6.2.2.5 Instream Habitat				
	6.3 Geomorphic Risk Assessment/Results				
	6.3.1 Methodology				
	6.3.1.1 Rapid Geomorphic Assessments				
	6.3.1.2 Planning-Level Channel Migration Zone Mapping				
	6.3.1.3 Community Asset Inventory				
	6.3.2 Geomorphic Risk Assessment				
	6.3.2.1 Rapid Geomorphic Assessment				
	6.3.2.1.1 RMNP Headwaters to Park Boundary				
	6.3.2.1.2 RMNP Boundary to Upper Fish Hatchery Road Crossing				
	6.3.2.1.3 Upper Fish Hatchery Road Crossing to Lower Fish Hatchery Road Crossing				
	6.3.2.1.4 Lower Fish Hatchery Road Crossing to Old Ranger Road				
	6.3.2.1.5 Old Ranger Road to West Elkhorn Ave.				
	6.3.2.1.6 West Elkhorn Ave. to Big Thompson River				
	6.3.2.2 Planning-Level Channel Migration Zone Mapping				
	6.3.2.2.1 Interpreting the pCMZ Maps and pCMZ Applications				
	6.3.2.2.2 RMNP Boundary to Upper Fish Hatchery Road Crossing				
	6.3.2.2.3 Upper Fish Hatchery Road Crossing to Lower Fish Hatchery Road Crossing				
	6.3.2.2.4 Lower Fish Hatchery Road Crossing to Old Ranger Road				

- 6.3.2.2.5 Old Ranger Road to West Elkhorn Ave.
- 6.3.2.2.6 West Elkhorn Ave. to Big Thompson River
- 6.3.2.3 Community Asset Inventory
- 6.4 Flood Risk Assessment
 - 6.4.1 Methodology
 - 6.4.1.1 Hydraulic Modeling
 - 6.4.1.1.1 CWCB 2013 Post-Flood Hydraulic Modeling
 - 6.4.1.1.2 Modified CWCB 2013 Post-Flood Hydraulic Modeling
 - 6.4.1.2 Community Asset Inventory
 - 6.4.2 Results
 - 6.4.2.1 Hydraulic Modeling
 - 6.4.2.1.1 Hydraulic Modeling Limitations and Assumptions
 - 6.4.2.2 Community Asset Inventory

- 7.2.2.5 Watershed Management Plans
- 7.2.2.6 Long Term River Monitoring
- 7.2.2.7 Flood Warning System
- 7.2.2.8 Join the National Flood Insurance Program (NFIP)
 - Community Rating System (CRS)
- 7.2.2.9 Stormwater Management and Accounting for Altered Hydraulic Regimes
- 7.2.2.10 Regulatory Frameworks and Funding Strategies
- 7.3 Recommended Projects
 - 7.3.1 Recommended Project Development
 - 7.3.2 Recommended Project Matrix
- 7.4 Prioritized Projects
 - 7.4.1 Overview
 - 7.4.2 Prioritized Project Cut Sheets

Section **7.0**

Recovery and Restoration Project Recommendations 41

- 7.1 Overview
 - 7.1.1 How to Use This Document
- 7.2 System Wide Recommendations
 - 7.2.1 Development Strategies
 - 7.2.1.1 Improve Channel Complexity and Function
 - 7.2.1.1.1 Create Compound Channels
 - 7.2.1.1.2 Create Complex “Messy Channels”
 - 7.2.1.2 Reduce Channelization, Armoring, and Floodplain Disconnections
 - 7.2.1.3 Improve and Relocate Road Infrastructure
 - 7.2.1.4 Improve Public and Private Crossings
 - 7.2.1.4.1 Increase Conveyance - Adjustments to Bridge Geometry Standards
 - 7.2.1.4.2 Maintain and Restore Sediment Transport Capacity
 - 7.2.1.4.3 Compound Channels Through the Crossing
 - 7.2.1.4.4 Additional Floodplain Conveyance
 - 7.2.1.4.5 Break-Away Bridges and Designed - to - Fail Approaches
 - 7.2.1.4.6 Shared Crossings
 - 7.2.1.4.7 Temporary Crossings
 - 7.2.1.5 Diversion/Utility Structure Strategies
 - 7.2.1.6 Relocate Utilities out of the River Corridor
 - 7.2.1.7 Multiple Lines of Defense
 - 7.2.2 Programs and Regulations
 - 7.2.2.1 Create a Protected “River Corridor”
 - 7.2.2.2 Finalize and Adopt Channel Migration Zone Delineations and Policy
 - 7.2.2.3 New Flood Insurance (FIS)
 - 7.2.2.4 Reducing Risk and Enhancing Ecosystems via Land Use and Zoning

Section **8.0**

Next Steps 121

- 8.1 Long Term Coalition Building and Engagement
- 8.2 Plan for Resiliency Implementation
 - 8.2.1 Coalition Leadership
 - 8.2.2 Potential Funding Sources
 - 8.2.3 National Flood Insurance Program

Section **9.0**

References 131

Section **10.0**

Appendices 133

- 10.1 Ecology Mapbook
- 10.2 CMZ Mapbook
- 10.3 Preliminary Floodplain Mapbook
- 10.4 Hydraulic Modeling Results
- 10.5 Community Comments